

I. GENERAL

The County of Norfolk is requesting bids for Repair and Resurfacing of Tennis Courts for the Wollaston Recreational Facility. Price is to include all labor and necessary materials required. The awarded contractor will be responsible for coordinating all necessary work. The work will be completed within thirty (30) days after a contract is awarded, unless mutually agreed upon by Norfolk County and the awarded contractor. The awarded contractor will be responsible for obtaining the appropriate permits and inspections (if applicable) from the City of Quincy. All work will be done to current code.

The contractor shall take reasonable precautions for safety, of, and shall provide reasonable protection to prevent damage, injury or loss to:

- employees on the Work and other persons who may be affected thereby;
- the Work and materials and equipment to be incorporated therein, whether in storage on or off the site, under care, custody or control of the Contractor
- other property at the site or adjacent thereto, such as trees, shrubs, lawns, walks, pavements, roadways, structures and utilities not designated for removal, relocation or replacement in the course of the work

The site must be left in a neat orderly fashion each day and must not interfere with the operation of the county.

III. SCOPE OF WORK

Four (4) bituminous concrete all-weather Tennis Courts and one (1) practice area Medium Bounce. Color to be determined

APPLICATION:

Furnish all labor, material and equipment to repair structural and random cracks using the Riteway Crack Repair (or equal) in bituminous concrete surface and apply a three (3) coat Acrylic Surface System as outlined below.

1. Two (2) sets, four (4) courts total 3200 square yards of Area – 1400 linear feet of crack repair and one 3025 sq. ft. practice court.
2. Remove vegetation, if any, from the cracks and thoroughly clean cracks with the use of brooms and air pressure.
3. Install a base in the cracks where needed
4. Fit all cracks with a court patch binder or concrete depending on the width of the cracks
5. Install the three (3) membrane layers of Riteway Crack Repair System (or equal) over filled cracks per manufacturer's specifications
6. Sweep and air clean areas to be surfaced
7. Apply two (2) coats of Latexite textured surface at a rate of approximately .05 gallon/SY per coat
8. Apply one (1) coat of Latexite finish applied at a rate of approximately .05 gallon/SY
9. Layout, mask and stripe playing lines with a paintbrush using 100% acrylic textured line paint.
10. Remove masking tape and clean up general work area.